

Phone: (215) 569-5618
Fax: (215) 832-5618
Email: MMontalbano@BlankRome.com

March 10, 2017

VIA ELECTRONIC FILING

Rosemary Chiavetta, Secretary
Pennsylvania Public Utility Commission
Commonwealth Keystone Building
400 North Street
Harrisburg, PA 17120


**Re: Respondent Sunoco Pipeline L.P.'s Motion To Strike Complainant's
Request for Attorneys' Fees, Docket No. C-2017-2589346**

Dear Secretary Chiavetta:

Enclosed for filing with the Commission is Sunoco Pipeline L.P.'s Motion to Strike Complainant's Request for Attorneys' Fees. Copies of the Motion have been mailed in accordance with the Certificate of Service.

Thank you for your attention to this matter, and please do not hesitate to contact me with any questions or concerns.

Very truly yours,



Michael Joseph Montalbano
Associate

MJM:bjc
Enclosures

cc: Christopher A. Lewis (*w/out enclosures*)

BLANK ROME LLP

Christopher A. Lewis (I.D. No. 29375)
Michael Montalbano (I.D. No 320943)
One Logan Square
130 N. 18th Street
Philadelphia, PA 19103
Phone: (215) 569-5500
Facsimile: (215) 832-5793
Email: Lewis@BlankRome.com
MMontalbano@BlankRome.com

*Attorneys for Defendant
Sunoco Pipeline L.P.*

WEST GOSHEN TOWNSHIP AND	:	
CONCERNED CITIZENS OF WEST	:	
GOSHEN TOWNSHIP	:	
	:	Docket No. C-2017-2589346
Complainant,	:	
	:	
v.	:	
	:	
SUNOCO PIPELINE L.P.,	:	
	:	
Respondent.	:	
	:	

NOTICE TO PLEAD

Pursuant to 52 Pa. Code § 5.103(c), you are hereby notified to file a written response to the enclosed motion within 20 days of the date of service hereof. Your response must be filed with the Secretary of the Pennsylvania Public Utility Commission, with a copy served to counsel for Sunoco Pipeline L.P., and where applicable, the Administrative Law Judge presiding over the issue.

File with:
Rosemary Chiavetta, Secretary
Pennsylvania Public Utility Commission
Commonwealth Keystone Building
400 North Street, Second Floor
Harrisburg, PA 17120

With a copy to:

Christopher A. Lewis, Esquire
Michael Montalbano, Esquire
Blank Rome LLP
One Logan Square
Philadelphia, PA 19103

Dated: March 10, 2017

Christopher A. Lewis

Christopher A. Lewis (I.D. No. 29375)

Michael Montalbano III (I.D. No. 320943)

One Logan Square

130 N. 18th Street

Philadelphia, PA 19103

(215) 569-5500

Lewis@BlankRome.com

MMontalbano@BlankRome.com

BLANK ROME LLP
Christopher A. Lewis (I.D. No. 29375)
Michael Montalbano (I.D. No 320943)
One Logan Square
130 N. 18th Street
Philadelphia, PA 19103
Phone: (215) 569-5500
Facsimile: (215) 832-5793
Email: Lewis@BlankRome.com
MMontalbano@BlankRome.com

*Attorneys for Defendant
Sunoco Pipeline L.P.*

**COMMONWEALTH OF PENNSYLVANIA
BEFORE THE
PENNSYLVANIA PUBLIC UTILITY COMMISSION**

WEST GOSHEN TOWNSHIP	:	
<i>Complainant</i>	:	
	:	
v.	:	Docket No. C-2017-2589346
	:	
SUNOCO PIPELINE, L.P.	:	
<i>Respondent</i>	:	
	:	

**SUNOCO PIPELINE L.P.’S
MOTION TO STRIKE COMPLAINANT’S
REQUEST FOR ATTORNEYS’ FEES**

Sunoco Pipeline L.P. (“SPLP”), by and through the undersigned counsel, and pursuant to § 5.103(a) of the Commission’s regulations, 52 Pa. Code § 5.103, files this Motion to Strike Complainants’ Request for Attorneys’ Fees.

I. INTRODUCTION

Complainant West Goshen Township (“WGT”) has asked the Public Utility Commission (the “Commission”) to assess the attorneys’ fees and costs WGT incurred in bringing this

Complaint, despite being well-aware that the Commission possesses no such authority. For decades, the Commission has repeatedly held that absent statutory authorization or an agreement between the parties, the Commission has no authority to award attorneys' fees. Still, WGT included this unfounded request without pointing to any statutory authority or agreement that authorizes such an award. The reason for WGT's omission is straightforward: No such authority or agreement exist. SPLP therefore requests that the Commission strike WGT's request for attorneys' fees and costs as it has no basis in the law.

II. STATEMENT OF FACTS

1. On June 15, 2015, WGT and SPLP entered into a Settlement Agreement, which resolved an outstanding dispute regarding the situation and construction of a building on property owned by SPLP near Boot Road. (*See* Ex. A ¶ I.A).

2. As set forth in paragraph II.A.7 of the Settlement Agreement, as part of its final design, SPLP planned to install remotely operated valves (controlled by its centralized control room) at pipeline markers 228 and 236.6. (*See id.* ¶ II.A.7).

3. Paragraph II.A.7 also states SPLP's plan to use commercially reasonable efforts to apply for any rights of way, approvals and extensions of utility service within sixty (60) days after the Effective Date of the Settlement Agreement, and to install the remotely operated valves within ninety (90) days after receipt of all necessary permits, rights of way, approvals, and extensions of utility service. (*See id.*).

4. SPLP maintains a manual valve at pipeline marker 236.6; however, the valve cannot yet be operated remotely because the extension of utility service required to supply electric power for the remote operation has not been completed.

5. On or around February 13, 2017, David Brooman, esq., counsel for the WGT spoke with SPLP's counsel telephonically.

6. During the conversation, Mr. Brooman indicated that WGT would file a Complaint, asking the Commission to enforce the Settlement Agreement, and order SPLP to pay the attorneys' fees of WGT that were incurred in bringing the Complaint.

7. In an effort to avoid needless litigation, SPLP's counsel sent a letter to Mr. Brooman on February 14, 2017, stating that SPLP "fully intends to live up to its plan, as stated in the Settlement Agreement, to automate the valve at pipeline market 236.6. Currently, SPLP expects the work on the valve to be completed by March 31, 2017." (*See Ex. B at 1*).

8. SPLP's counsel also noted that the Commission has no authority to award attorneys' fees or costs, and that the expense of the litigation would fall on the taxpayers of WGT. (*See id.*).

9. On February 21, 2017, SPLP was served with a Formal Complaint filed by WGT.¹ (*See Feb. 17, 2017 Formal Compl., Docket No. C-2017-2589346*).

10. In the Complaint, WGT requests, *inter alia*, "an assessment of counsel fees and other costs incurred by the Township in bringing this Formal Complaint to Enforce the Settlement Agreement. (*See id.* at 5, 9).

¹ The case caption on WGT's Complaint also lists Concerned Citizens of West Goshen Township ("CCWGT"). SPLP respectfully requests that CCWGT be stricken from WGT's case caption because CCWGT has not joined this action.

III. ARGUMENT

11. Pennsylvania case law makes clear that absent express statutory authority or an agreement by the parties, one party cannot recover attorneys' fees and costs from the opposing party. *See Corace v. Balint*, 210 A.2d 882, 886 (Pa. 1965) ("Over and over again we have decided there can be no recovery for counsel fees from the adverse party to a cause, in the absence of express statutory allowance of the same, or clear agreement by the parties (internal citations omitted)).

12. The Commission itself has consistently held that it has no authority to award attorneys' fees and costs. *See Edward Kovler & Elena Glozman v. PECO Energy Co.*, C-2013-2365555, 2013 WL 6248460, at *4 (Pa. Pub. Util. Comm'n Nov. 18, 2013) ("Nothing in the Public Utility Code, the Commission's regulations or orders gives the Commission the power to grant attorney fees in this case."); *Mci Worldcom, Inc. v. Bell Atlantic-Pa.*, 94 Pa. P.U.C. 509 (Pa. Pub. Util. Comm'n Dec. 21, 2000) ("The Commission does not have jurisdiction to award attorney's fees and costs."); *Pennsylvania Pub. Util. Comm'n v. Nat'l Fuel Gas Distribution Corp.*, 63 Pa. P.U.C. 68 (Pa. Pub. Util. Comm'n Jan. 8, 1987) ("[W]e have recently held that (1) that we have no statutory authority to award attorney fees, and (2) that we also lack the equitable power necessary to grant an award of attorneys' fees and costs."); *Pennsylvania Pub. Util. Comm'n v. Duques*, 61 Pa. P.U.C. 485 (Pa. Pub. Util. Comm'n May 15, 1986) ("We agree that the Public Utility Commission, as a creature of the Legislature, has only those powers which the Legislature has granted it. [Petitioner] has pointed to no statute concerning this matter which authorizes the payment of attorney's fees to the successful litigant")

13. Despite being well-aware that the Commission cannot award attorneys' fees, WGT has requested such an award in its Complaint. (*See* Feb. 17, 2017 Formal Compl., Docket No. C-2017-2589346 at 5, 9).

14. Further, WGT has not pointed to any statute, regulation, or agreement that might authorize the Commission to award attorneys' fees and costs as none exist.

15. Accordingly, WGT's request has no basis in the law, and SPLP respectfully submits that the request be stricken from the Complaint.

IV. **CONCLUSION**

16. For the foregoing reasons, WGT's request for attorneys' fees and costs should be stricken from the Complaint.

Respectfully submitted,

BLANK ROME LLP

Dated: March 10, 2017

/s/ Christopher A. Lewis
Christopher A. Lewis (I.D. No. 29375)
Michael Montalbano III (I.D. No. 320943)
One Logan Square
130 N. 18th Street
Philadelphia, PA 19103
(215) 569-5500
Lewis@BlankRome.com
MMontalbano@BlankRome.com

BLANK ROME LLP
Christopher A. Lewis (I.D. No. 29375)
Michael Montalbano (I.D. No 320943)
One Logan Square
130 N. 18th Street
Philadelphia, PA 19103
Phone: (215) 569-5500
Facsimile: (215) 832-5793
Email: Lewis@BlankRome.com
MMontalbano@BlankRome.com

*Attorneys for Defendant
Sunoco Pipeline L.P.*

WEST GOSHEN TOWNSHIP AND
CONCERNED CITIZENS OF WEST
GOSHEN TOWNSHIP
Complainant,
v.
SUNOCO PIPELINE L.P.,
Respondent.

Docket No. C-2017-2589346

Verification

I, Harry J. Alexander, Vice President of Business Development for Sunoco Pipeline L.P., being fully authorized to make this Verification on behalf of Sunoco Pipeline L.P., states the facts set forth above in the attached Motion to Strike Complainant's Request for Attorneys' Fees are true and correct to the best of my knowledge, information, and belief, and I expect to be able to prove the same at a hearing held in this matter. I understand that the statements herein are made subject to the penalties of 18 Pa. Cons. Stat. § 4904 (relating to unsworn falsification to authorities).

Dated: March 9, 2017



HARRY J. ALEXANDER

CERTIFICATE OF SERVICE

I, Michael J. Montalbano, hereby certify that on this 10th day of March, 2017, pursuant to 52 Pa. Code § 1.54 (relating to service by a party), I caused a true copy of Sunoco Pipeline L.P.'s Motion to Strike Complainant's Request for Attorneys' Fees to be served upon the parties listed below by electronic mail and U.S. Mail, first-class, postage prepaid, and by filing it electronically with the Commission:

David Brooman, Esquire
Douglas Wayne, Esquire
High Swartz, LLP
40 East Airy Street
Norristown, PA 19404
dbrooman@highswartz.com
dwayne@highswartz.com

Michael J. Montalbano

Michael J. Montalbano
Attorney for Sunoco Pipeline L.P.

Exhibit A

PENNSYLVANIA PUBLIC UTILITY COMMISSION

CERTIFICATE OF FILING


Agreement between the Township, Sunoco Pipeline LP and the local group of concern citizens of West Goshen Township.

U-2015-2486071

BY THE COMMISSION:

AND NOW, June 15, 2015, the Public Utility Commission certifies that the above, captioned contract or indenture dated May 13, 2015 has been on file with the Commission since May 15, 2015, in accordance with Section 507 of the Public Utility Code, 66 Pa. C.S. §507.

PENNSYLVANIA PUBLIC UTILITY COMMISSION



Secretary

PROPOSED SETTLEMENT AGREEMENT -- NOT FINAL UNTIL SIGNED BY ALL
PARTIES

SETTLEMENT AGREEMENT

This Agreement is made by, between, and among Sunoco Pipeline, L.P., a limited partnership organized under the laws of the State of Texas ("SPLP"); West Goshen Township, a Township of the Second Class located in Chester County, Pennsylvania ("WGT"); and, Concerned Citizens of West Goshen Township, an ad hoc association of individual persons each of whom owns and resides on property adjacent to or within approximately 1,000 feet of the properties owned by SPLP near Boot Road in WGT ("CCWGT"), hereinafter collectively referred to as the "Parties."

I. Background

A. On March 21, 2014, Sunoco filed a Petition with the Pennsylvania Public Utility Commission ("Commission") requesting, inter alia, approval for the situation and construction of a building on property owned by SPLP near Boot Road in WGT to house facilities related to a pump station ("SPLP Petition"). The Boot Road Pump Station, and an associated Vapor Combustion Unit ("VCU"), would serve a natural gas liquids pipeline owned by SPLP that is part of a project commonly known as Mariner East, which would transport propane, ethane, and other natural gas liquids from points west and north of WGT to points in Delaware County, Pennsylvania, and the State of Delaware. The Commission docketed the proceeding at P-2014-2411966.

B. On April 18, 2014, CCWGT filed a Protest and Preliminary Objections to the SPLP Petition. On April 21, 2014, WGT intervened as of right in the Commission docket.

C. In response to the Preliminary Objections of CCWGT and other parties, SPLP filed an Amended Petition against which further preliminary objections were filed by CCWGT, WGT, and other parties.

PROPOSED SETTLEMENT AGREEMENT -- NOT FINAL UNTIL SIGNED BY ALL
PARTIES

D. After the exchange of various other pleadings, the Commission issued an Opinion and Order dated October 29, 2014, that denied all preliminary objections and returned the matter to the Office of Administrative Law Judge for further proceedings.

E. On November 7, 2014, CCWGT filed a Formal Complaint with the Commission against SPLP concerning alleged safety concerns with proposed SPLP facilities in WGT, docketed at C-2014-2451943 ("CCWGT Complaint"). After the exchange of various pleadings, the Administrative Law Judges assigned to the CCWGT Complaint denied SPLP's preliminary objections to the Complaint and denied CCWGT's request to consolidate its Complaint with the SPLP Petition.

F. Subsequent to, and as a result of, these procedural matters, the Parties exchanged information (both formally and informally) and conducted settlement negotiations in an attempt to resolve this litigation and related matters.

II. Pertinent Information Provided by SPLP

A. SPLP has provided WGT and WGT's consulting expert with the following information ("SPLP Information"). WGT and CCWGT expressly rely upon the accuracy of the SPLP Information in reaching this Agreement.

1. As used herein, the phrase "Mariner East Project" refers to the existing Mariner East 1 pipeline and appurtenant facilities, and all additional pipelines and appurtenant facilities to be owned and/or operated by SPLP in WGT for the transportation of propane, ethane, butane, and/or other natural gas liquids.

2. The pump station, the VCU and all accessory and appurtenant above-ground facilities associated with all phases of the Mariner East Project will be maintained within the present active site, Parcel No. 52-1-8-U, on which the existing Boot Road Pump Station

PROPOSED SETTLEMENT AGREEMENT -- NOT FINAL UNTIL SIGNED BY ALL
PARTIES

currently operates (the "SPLP Existing Site"), except that a remote operated valve station will be constructed and maintained on SPLP's adjacent 4.42 acre property, Parcel No. 52-0-10-10.1, also known as the former Janiec Tract, (the "SPLP Additional Acreage"). The proposed location of such valve station on the SPLP Additional Acreage is depicted on the map attached hereto as Appendix 1 and incorporated by reference (the "SPLP Use Area"). Subject to any engineering constraints, SPLP intends to construct the valve station in the general area depicted on the map attached hereto as Appendix 1. If due to engineering constraints, SPLP is unable to construct the valve station in the SPLP Use Area, SPLP will notify WGT. Nothing in this Settlement Agreement constitutes an authorization or agreement for SPLP to construct the valve station in any location on the SPLP Additional Acreage other than in the SPLP Use Area.

3. As of the date of execution of this Agreement, SPLP has no plan or intention to construct any additional above-ground permanent utility facilities in WGT except as otherwise expressly set forth in this Agreement.

4. Consistent with its engineering plans for all Mariner East 1 pump stations, there will be an enclosed VCU at the Boot Road Pump Station. The location of the VCU on the SPLP Existing Site will be as noted on the map provided to WGT and CCWGT attached hereto as Appendix 2 and incorporated by reference. The VCU is designed and will be constructed and operated to contain any pilot light or flame completely within its structure such that no flame is visible outside the pump station site except in rare instances. In the event of a rare instance in which a flame is visible, in addition to first responders and emergency responders to which SPLP currently provides notification, SPLP shall notify the WGT Township Manager of the circumstances causing the flame to be visible.

PROPOSED SETTLEMENT AGREEMENT -- NOT FINAL UNTIL SIGNED BY ALL
PARTIES

5. The VCU is designed so that the anticipated noise level at a distance of 145 feet is 51.3 decibels, as shown on the noise diagram provided by SPLP to WGT and CCWGT attached hereto as Appendix 3 and incorporated by reference.

6. As is the case for all of its products pipelines, the Mariner East Project present and proposed pipelines are included within SPLP's current rupture monitoring system which has several alarms designed for different pipeline conditions and events. Included in SPLP's rupture monitoring system is the Inter Site Automatic Close Logic system (ISACL), a first line of defense automated alarm system designed to automatically shut-down the pipeline and close remotely operated valves on the mainline in the event of a rupture or low pressure on the pipeline. Each individual Mariner East Project pipeline station shall be equipped with an automated shutdown and upset condition response logic that is triggered for all or any segment of the Mariner East Project. If triggered, the pipeline or a segment of the pipeline shall be automatically shut-down and the remotely operated valves impacting the mainline pipeline closed, with no operator discretion. The ISACL system can be triggered by other locations on the pipeline or can be initiated locally and it will trigger events at other pipeline locations.

7. SPLP currently maintains remotely operated inlet and outlet valves at its Boot Road Pump Station in WGT that are controlled by a centralized control room, and these valves will be used in connection with the Mariner East Project. In addition, SPLP maintains a number of remotely operated valves and manual valves, including manual valves at pipeline markers 228 and 236.6 (the pipeline valve locations immediately upstream and downstream from Boot Road) in connection with its Mariner East Project. As part of its final design, SPLP is installing remotely operated valves that are controlled by its centralized control room at pipeline markers 228 and 236.6. SPLP will use commercially reasonable efforts to apply for any permits,

PROPOSED SETTLEMENT AGREEMENT -- NOT FINAL UNTIL SIGNED BY ALL
PARTIES

rights of way, approvals and extensions of utility service within sixty (60) days after the Effective Date of this Agreement. These remotely operated valves will be installed within ninety (90) days after receipt of all necessary permits, rights of way, approvals, and extensions of utility service.

III. WGT's Safety Review.

1. WGT has engaged Accufacts, Inc., and its President, Richard Kuprewicz, a nationally recognized expert in the field of liquids pipeline safety, to prepare a written report as to the safety of Mariner East 1 (the "Kuprewicz Report") based on the design and engineering facts and information heretofore provided by SPLP. The Kuprewicz Report is attached as Appendix 5 hereto and is made a part of this Agreement.

IV. The Parties' Promises, Covenants and Agreements

A. Based on the SPLP Information recited in Section II of this Agreement, the Parties agree to make the following promises, covenants and agreements:

1. SPLP covenants and agrees as follows:

a. Because of its existing Pump Station Facility at Boot Road, except with respect to the SPLP Use Area, SPLP covenants and agrees that it shall not construct or install any pump stations, VCUs or above-ground permanent public utility facilities on the SPLP Additional Acreage for any phase of the Mariner East Project. SPLP also agrees that, except for the SPLP Use Area, any use of the SPLP Additional Acreage for staging construction, laydown or other operational activity will be temporary, and SPLP will restore the surface to its former condition following the completion of such activity. SPLP will execute and record a deed restriction reflecting this limitation within sixty (60) days of the Effective Date of this Agreement, in a form substantially similar to the Form of Deed Restriction attached hereto as

**PROPOSED SETTLEMENT AGREEMENT -- NOT FINAL UNTIL SIGNED BY ALL
PARTIES**

Appendix 4. SPLP will provide copies of the recorded deed restriction to counsel for WGT and CCWGT within five business days of the date of recording.

b. SPLP will provide the WGT Township Manager with immediate notice of any Mariner East pipeline condition changes requiring remediation under 49 CFR Section 195.452(h)(4)(i), (ii), (iii) or (iv) that potentially could impact WGT, and thereafter will provide a written report within thirty (30) days describing the remediation efforts undertaken by SPLP, the location of the remediation efforts, and the expected timeframe within which these remediation efforts will be completed.

c. Within thirty (30) days after the Effective Date of this Agreement, SPLP agrees to consult with WGT officials concerning land development plans, including landscaping and fencing plans, with respect to the SPLP Existing Site and the SPLP Additional Acreage and to provide WGT officials with any existing landscaping or screening plans for such areas.

2. WGT covenants and agrees as follows:

a. WGT shall not oppose the thirty-four feet (34') height proposed for the VCU.

b. WGT consents to the withdrawal by SPLP of the SPLP Petition now pending before the Commission, and will not initiate any action or proceeding claiming that the existing or reconfigured pump station at Boot Road violates WGT's zoning or land development ordinances.

c. For so long as SPLP offers to provide intrastate petroleum and refined petroleum products pipeline service to the public, including transportation of propane or ethane, WGT will not contest, dispute or protest SPLP's service for lack of public utility status in

PROPOSED SETTLEMENT AGREEMENT -- NOT FINAL UNTIL SIGNED BY ALL
PARTIES

any federal, state, local or regulatory proceeding or file any lawsuit, litigation or action or join any lawsuit, litigation or action with respect thereto.

d. As long as SPLP (i) constructs and operates facilities in WGT as described in Section II above; (ii) abides by the covenants and agreements in Section III.A.1 above; and (iii) operates in a manner consistent with the safety, design and engineering facts and information heretofore provided to WGT's consultant, WGT agrees that it will not file or join in any complaint against the safety of SPLP's service or facilities with the Commission or any other federal, state or local government agency or endorse or promote any protest or action filed by the CCWGT or any other individual or group against SPLP with respect to the safety of Mariner East 1 or the valve station described in paragraph II.A.2. of this Agreement.

e. With respect to Mariner East 2, SPLP agrees, upon the execution of a mutually agreeable confidentiality agreement, that it will provide to Accufacts, Inc. or a person or entity acting for WGT that is similarly a nationally recognized expert in the field of liquids pipeline safety ("Liquids Pipeline Safety Expert") information relating to Mariner East 2 of a similar nature that was provided regarding Mariner East 1 for review by the Liquids Pipeline Safety Expert. WGT and its expert will meet and confer with SPLP with respect to any concerns the Liquids Pipeline Safety Expert may have related to safety and SPLP will be provided an opportunity to respond thereto, before WGT would file any formal protest or other action raising any safety issue related to Mariner East 2.

f. WGT will treat as public information any notifications provided to the Township Manager by SPLP concerning (1) the circumstances causing the visibility of a flame from the VCU, or (2) Mariner East Project pipeline condition changes requiring remediation under 49 CFR Section 195.452(h)(4)(i), (ii), (iii) or (iv), and will make such

PROPOSED SETTLEMENT AGREEMENT -- NOT FINAL UNTIL SIGNED BY ALL
PARTIES

information available to members of the public in accordance with standard WGT procedures for access to public information.

3. CCWGT covenants and agrees as follows:

- a. The members of CCWGT are identified in Appendix 6 attached hereto.
- b. CCWGT consents to the withdrawal by SPLP of the SPLP Petition now pending before the Commission and will not initiate any action or proceeding claiming that the existing or reconfigured pump station at Boot Road violates WGT's zoning or land development ordinances.
- c. For so long as SPLP offers to provide intrastate petroleum and refined petroleum products pipeline service to the public, including transportation of propane or ethane, CCWGT will not contest, dispute or protest SPLP's service for lack of public utility status in any federal, state, local or regulatory proceeding or file any lawsuit, litigation or action or join any lawsuit, litigation or action with respect thereto.
- d. Within five (5) business days after the Effective Date, CCWGT agrees to mark as satisfied and withdraw the CCWGT Complaint.
- e. As long as SPLP (i) constructs and operates facilities in WGT as described in Section II above; (ii) abides by the covenants and agreements in Section III.A.1 above; and (iii) operates in a manner consistent with the safety, design and engineering facts and information heretofore provided to WGT's consultant, CCWGT agrees that it will not file or join in any complaint against the safety of SPLP's service or facilities with the Commission or any other federal, state or local government agency or endorse or promote any protest or action filed

PROPOSED SETTLEMENT AGREEMENT -- NOT FINAL UNTIL SIGNED BY ALL
PARTIES

by any other individual or group against SPLP with respect to the safety of Mariner East 1 or the valve station described in paragraph II.A.2. of this Agreement.

V. General Provisions

A. In addition to the individual promises, covenants and agreements set forth above, the Parties individually and jointly acknowledge and agree as follows:

1. This Agreement is an agreement between a public utility and a municipal corporation that must be filed with the Commission at least 30 days prior to its effective date in order to be legally valid and binding, as set forth in 66 Pa. C.S. § 507. The Parties agree, therefore, that this Agreement shall be filed by SPLP with the Commission within five calendar days after it is duly executed by all parties. The Parties further agree to fully support this Agreement in any proceeding instituted by the Commission concerning this Agreement, and to refrain from taking any position before the Commission that is contrary to, or inconsistent with, the terms and conditions of the Agreement.

2. The Parties acknowledge and agree that the Effective Date of this Agreement shall be the date which is 35 calendar days after the last date on which the Agreement is executed by all Parties, as shown below.

3. The Parties acknowledge and agree that any action to enforce the deed restriction on the use of the SPLP Additional Acreage shall be brought before the Chester County Court of Common Pleas.

4. The Parties acknowledge and agree that any action to enforce any provision of this Agreement (other than the deed restriction on the use of the SPLP Additional Acreage) shall be brought before the Pennsylvania Public Utility Commission or any such successor agency or commission.


PROPOSED SETTLEMENT AGREEMENT -- NOT FINAL UNTIL SIGNED BY ALL PARTIES

5. This Agreement shall be binding on the Parties, their successors and assigns.

6. This Agreement may be executed in one or more counterparts, each of which is an original and all of which together constitute one and the same instrument.

IN WITNESS WHEREOF, the parties have executed or caused this Agreement to be executed as of the dates shown below.

SUNOCO PIPELINE, L.P.

By: 

Date: 4-14-15

Attest: Kathleen Shea Belley

Counsel: _____

WEST GOSHEN TOWNSHIP, CHESTER COUNTY, PENNSYLVANIA

By: Name: _____
Title: Chairman, Board of Supervisors

Date: _____

Attest: _____

Special Counsel: _____

CONCERNED CITIZENS OF WEST GOSHEN TOWNSHIP

By: Name: _____
Duly authorized representative of CCWGT

Date: _____

Attest: Scott J. Rubin, Esq.
Counsel for CCWGT

PROPOSED SETTLEMENT AGREEMENT -- NOT FINAL UNTIL SIGNED BY ALL PARTIES

5. This Agreement shall be binding on the Parties, their successors and assigns.

6. This Agreement may be executed in one or more counterparts, each of which is an original and all of which together constitute one and the same instrument.

IN WITNESS WHEREOF, the parties have executed or caused this Agreement to be executed as of the dates shown below.

SUNOCO PIPELINE, L.P.

By: _____

Date: _____

Attest: _____

Counsel: _____

WEST GOSHEN TOWNSHIP, CHESTER COUNTY, PENNSYLVANIA


By: Name: _____

Date: May 13, 2015

Title: Chairman, Board of Supervisors

Attest: _____

Special Counsel: _____

CONCERNED CITIZENS OF WEST GOSHEN TOWNSHIP

By: Name: _____
Duly authorized representative of CCWGT

Date: _____

Attest: _____
Scott J. Rubin, Esq.
Counsel for CCWGT

**CONFIDENTIAL SETTLEMENT DOCUMENT
NOT FOR PUBLIC DISTRIBUTION UNTIL SIGNED BY ALL PARTIES**

6. This Agreement may be executed in one or more counterparts, each of which is an original and all of which together constitute one and the same instrument.

IN WITNESS WHEREOF, the parties have executed or caused this Agreement to be executed as of the dates shown below.

SUNOCO PIPELINE, L.P.

By: _____ Date: _____

Attest: _____

Counsel:

WEST GOSHEN TOWNSHIP, CHESTER COUNTY, PENNSYLVANIA


By: Chairman, Board of Supervisors _____ Date: _____

Attest: _____

Special Counsel:

CONCERNED CITIZENS OF WEST GOSHEN TOWNSHIP

By:  _____ Date: 04/11/2025
Duly authorized representative of CCWGT
Raymond Allen

Attest:  _____
Scott J. Rubin, Esq.
Counsel for CCWGT

**PROPOSED SETTLEMENT AGREEMENT -- NOT FINAL UNTIL SIGNED BY ALL
PARTIES**

Appendices:

- Appendix 1: Map showing SPLP Use Area**
- Appendix 2: Map showing location of VCU**
- Appendix 3: VCU noise diagram**
- Appendix 4: Form of Deed Restriction**
- Appendix 5: Kuprewicz Report**
- Appendix 6: List of members of CCWGT and signatures/initials of members (at least 51%)
approving the Settlement Agreement**


APPENDIX 1

Map Showing SPLP Use Area

APPENDIX 2

Map Showing Location of VCU

Appendix 2



		DRAWING NO. 2886-BOO2-EXHIBIT 1 SHEET NO. E1
BOOT STATION GENERAL ARRANGEMENT		PROJECT NO. 2886-BOO2-EXHIBIT 1 DATE 11/11/11
PROJECT LOCATION D.C. OVERSEAS (DC)		DRAWING TITLE BOOT STATION GENERAL ARRANGEMENT
PROJECT MANAGER DAVID W. BERRY		PROJECT NO. 2886-BOO2-EXHIBIT 1
PROJECT ENGINEER DAVID W. BERRY		PROJECT DATE 11/11/11
PROJECT CHECKER DAVID W. BERRY		PROJECT STATUS COMPLETE
PROJECT APPROVER DAVID W. BERRY		PROJECT REVISIONS 1
PROJECT REVIEWER DAVID W. BERRY		PROJECT SCALE AS SHOWN
PROJECT DATE 11/11/11		PROJECT SHEET NO. E1

NOTES:
1. CONTRACTOR SHALL VERIFY ALL DIMENSIONS

APPENDIX 3

VCU Noise Diagram

61.3 dBA @ 46 ft

SEE DWG 2898-B002-M040400

85 dBA @ 3 ft

UNDERGROUND
DRP HEADER

FIELD VERIFY


SEE DWG 2898-B002-M040500

FLARE
SEE "T" FIELD VERIFY

SYSTEMS "T"
RECEIVER

PROPERTY LINES

11'-0"



APPENDIX 4
Form of Deed Restriction

DECLARATION OF RESTRICTIONS

THIS DECLARATION OF RESTRICTIONS is made as of this ___ day of _____, 2015, by SUNOCO PIPELINE, L.P., a Texas limited partnership ("Declarant")

BACKGROUND

A. Declarant is the owner of certain real property more particularly described on Exhibit A attached hereto (the "Subject Property").

B. Declarant desires to restrict the use of a portion of the Subject Property as more fully described on Exhibit B attached hereto ("Restricted Parcel 1").

C. Declarant desires to restrict the use of the balance of the Subject Property (*i.e.*, excluding Restricted Parcel 1) as more fully described on Exhibit C attached hereto ("Restricted Parcel 2").

NOW THEREFORE for good and valuable consideration and intending to be legally bound, Declarant hereby declares as follows:

1. Declarant covenants and agrees that it shall not construct or install any pump stations, vapor combustion units or above-ground permanent public utility facilities on Restricted Parcel 1.

2. Notwithstanding the foregoing, Declarant shall be permitted to use all or portions of Restricted Parcel 1 for staging construction, laydown or other operational activity on a temporary basis, and Declarant will restore the surface to its former condition following the completion of such activity.

3. Declarant covenants and agrees that the only public utility purposes that shall be permitted on Restricted Parcel 2 are the following purposes: (1) construction, maintenance, repair and/or replacement of a valve station for the Mariner East Project; and (2) staging construction, laydown or other operational activity on a temporary basis provided that Declarant restores the undeveloped surface of Restricted Parcel 2 to its former condition following the completion of such activity.

4. The restrictions set forth herein shall be binding on the Declarant, its successors and assigns, and shall run with the land.

5. This Declaration shall be governed by the laws of the Commonwealth of Pennsylvania

EXHIBIT A

Legal Description of the Subject Property

EXHIBIT B

Legal Description of Restricted Parcel 1

EXHIBIT C

Legal Description of Restricted Parcel 2

APPENDIX 5
Kuprewicz Report

Accufacts Inc.
"Clear Knowledge in the Over Information Age"

4643 192nd Dr. NE
Redmond, WA 98074
Ph (425) 836-4041
Fax (425) 836-1982
kuprewicz@comcast.net

Date: March 6, 2015

**To: Mr. Casey LaLonde
Township Manager
West Goshen Township
1025 Paoli Pike
West Chester, PA 19380-4699**

Re: Accufacts Report on Mariner East Project Affecting West Goshen Township

1. Introduction

Accufacts Inc. ("Accufacts") was asked to assist West Goshen Township ("Township") in evaluating a Sunoco Pipeline L.P. ("Sunoco") pipeline project identified as Mariner East, a project to repurpose an existing 8-inch pipeline and to modify an existing pump station within the Township to reverse flow and carry highly volatile liquids, or HVLs, eastward. Accufacts provides specialized technical and safety expertise in pipeline and pump station siting, design, operation/maintenance, and regulatory requirements, especially as it relates to HVLs, a category of liquids given special definition and regulation in the federal pipeline safety regulations.¹ Accufacts assisted the Township's legal team in collecting relevant technical information from Sunoco regarding the design and operation of the proposed Mariner East phase 1 ("Mariner East") pipeline project, and provided advice as to the safety and adequacy of Sunoco's approach, recommending several enhancements. Attachment 1 sets forth the list of confidential documents provided by Sunoco and reviewed by Accufacts.

The discussion and conclusions in this report are based on a careful review and analysis of the information provided by Sunoco to the representatives of the Township and to Accufacts. Accufacts understands that the Township is considering entering an agreement with Sunoco that codifies in writing the important safety systems and operating methods that factor into the conclusions reached in this report. Accufacts and the Township legal team were required to sign Nondisclosure Agreements ("NDA") with Sunoco that prevent Accufacts from disclosing certain sensitive information unless it is already in the public domain. While this

¹ 49CFR§195.2 Definitions.
Accufacts Inc.

limitation does not restrict Accufacts' ability to present its independent critical observations, the reader should be aware of the obligation to honor the NDA as Accufacts will not disclose certain sensitive details supporting our observations.

Accufacts' analysis and this report are limited to the segments of the Mariner East project that could affect the Township. Certain additional equipment physically outside of the Township was also reviewed, such as the overall control program, mainline valves, metering, and pump stations that could impact the Township in case of a release of HVL.

The Mariner East Pipeline crosses slightly over a mile of the Township as an 8-inch pipeline, primarily consisting of pipe manufactured in 1968, and newer pipe replacement segments, with the Boot Road Pump Station located within the Township that will be modified to allow the flow of HVLs consisting of ethane, propane or a mixture. These fluids are pressurized to remain liquid at operating conditions within the pipeline, but upon release would generate heavier than air hydrocarbon vapor clouds that can impact large areas. It is important that such a pipeline operation pay special attention to its design, operation, and maintenance practices to assure the pipeline's integrity to keep the fluid within the pipeline.

Federal pipeline safety regulations provide limited levels of safety assurance. Prudent pipeline operators moving HVLs should exceed these basic requirements to assure proper control of their system. These liquid pipeline safety regulations are codified in the Code of Federal Regulation ("CFR") at 49CFR§191, 49CFR§194, and 49CFR§195. The Federal pipeline safety regulations place the responsibility of safe pipeline operation squarely upon the pipeline operator. Many process safety management approaches have been codified into pipeline safety regulations under the label "integrity management," following a series of tragic pipeline ruptures. These high profile rupture failures have called into question the dedication of certain operators to comply with the intent of the safety regulations, especially in the area of integrity management.

I have observed over more than 40 years of incident investigations that some pipeline operators embrace the process safety management intent (or safety culture) to assure that they have their pipelines under control, while others do not. Accufacts has developed a series of process safety management questions concerning pipeline siting, design, operation, maintenance and performance standards that allow Accufacts to evaluate whether a pipeline operator is incorporating prudent management approaches to stay ahead of pipeline failures, especially ruptures. Ruptures are large volume releases associated with big openings typically from pipe fracture. It is not that difficult for an experienced pipeline person to readily ascertain if a pipeline operator embraces the process safety management approach to pipeline safety. The following general observations follow a process safety management

approach that I have successfully utilized over 40 years evaluating many complex operations, including pipelines.

2. Verification of Integrity of the Pipeline for High Pressure HVL Service

Pipe steel, even pipe steel manufactured over 80 years ago, does not age or wear out. Pipe steel has essentially an infinite life if properly assessed, maintained, and operated within its design parameters. Certain manufacturing processes and/or transportation, and construction techniques associated with older vintage pipe steel, as well as new pipe, can introduce some types of anomalies or imperfections that can grow to failure with time, such as cracks in pipelines. These imperfections are often associated with vintage electric resistance welded pipe, either low frequency (LF-ERW) or early high frequency (HF-ERW) pipe, that can exhibit axial crack rupture failure with time for various reasons. Also, after a pipeline is installed, certain imperfections can be introduced such as corrosion or third party damage that may merit that a particular segment of the pipeline be remediated or replaced. Additional pipe segments may also require replacement and relocation because of roadwork or other activities that have nothing to do with the condition of the pipeline. There are such pipe segments crossing the Township that replace the originally installed 8-inch pipe.

Federal pipeline safety regulatory advancements promulgated in the early 2000s, adopted as a result of some tragic transmission pipeline ruptures, improved on pipeline integrity assessments.² In addition, to the published regulations, the federal office responsible for pipeline safety, the Pipeline and Hazardous Materials and Safety Administration, or PHMSA, has issued Advisory Bulletins that can be implemented more quickly than the long process associated with regulation development.

One Advisory Bulletin especially significant in this matter is PHMSA's recently released bulletin addressing "repurposing," a change in service or reversal of flow in older pipelines.³ This Bulletin provides guidance on the use of important hydrotesting assessment procedures utilizing a strength and spike test.

Federal regulations do not currently specify the hydrostatic strength test as a percent of specified minimum yield strength, "%SMYS," or require the use of an additional hydrotesting protocol known as a "spike" test which is very important in evaluating many pipe steels. The above referenced Bulletin indicates: "Operators should consider performing ILI and {emphasis added} hydrostatic pressure with a spike test prior to implementing any

² 49CFR§195.452 Pipeline integrity management in high consequence areas.

³ PHMSA Advisory Bulletin, ADB-2014-04, "Pipeline Safety: Guidance for Pipeline Flow Reversals, Product Changes and Conversion to Service – Docket No. PHMSA-2014-0040," September 18, 2014.

of these changes, especially if historical records have indications of previous in-service or hydrostatic pressure test failures, selective seam corrosion, stress corrosion cracking, other cracking threats or other system concerns. A spike test 30 minutes in duration at 100 percent to 110 percent specified minimum yield strength or {emphasis added} between 1.39 to 1.5 times ...the maximum operating pressure for hazardous liquids is suggested as it is the best method for evaluating cracking threats at this time."

ILI stands for inline inspection, which involves the insertion, typically in an operating pipeline, of a "pig," a self-contained multi-ton device containing: a) measurement instruments, b) computers, c) storage devices to retain the information gathered, and d) batteries to support the remote device's gathering and retaining certain information about the pipeline's condition. Such ILI tools, also known as "smart pigs," are designed to measure various types of imperfections in the pipe, such as possible damage, corrosion, and with more recent developing technology, some types of crack threats. After a pig run is completed, the volume of ILI tool information must be further analyzed and evaluated off site by special analysts from the vendor supplying the ILI tool who utilize special proprietary software to determine which measured imperfections might be problematic (go to failure) before the next ILI tool run. This last step can take some time, involving months depending on the type of smart pig utilized and the amount/complexity of information gathered. Not all ILI tool runs are successful, especially if an ILI tool has not been proven field reliable for the type of threat, so a measure of precaution is warranted in ILI selection and subsequent analysis.

The best assessment method for ascertaining the suitability or integrity of the pipeline for its new service, especially if cracking threats may be present, are proper hydrotests performed in excess of the current minimum federal pipeline safety hydrotesting regulations that are meant for new pipe testing. Hydrotesting is superior due to its ability to assess/proof various forms of pipe crack threats particularly those cracks associated with certain types of vintage pipe that can grow over time to rupture failure, as ILI and associated engineering analyses has not yet proven sufficiently reliable to adequately assess. A prudent hydrotest (in excess of current federal pipeline safety regulations), is the proof test for cracking anomaly risks, given that ILI tools and related engineering assessments for discovering cracking potential are still in development.

Accufacts has reviewed the various types of ILI smart pig tools used to re-qualify the pipeline on the Mariner East project, and has carefully reviewed in detail the November 2014 hydrotest results provided by Sunoco on the segments that could affect the Township. Sunoco performed both strength and spike hydrotests. Accufacts can report that Sunoco tracked the percent minimum and maximum specified minimum yield strength, or %SMYS, during both the strength and the spike test phases of the hydrotesting. Hydrotesting pressures substantially exceeded the minimum 125 percent (1.25 times the maximum operating

pressure, or MOP) required in current federal regulations. These tests meet the test ranges identified in the above referenced Advisory Bulletin (at least 1.39 times MOP).⁴ It should be noted that the maximum operating pressure on the 8-inch pipeline will be quite high, so hydrotesting pressures as a ratio of MOP were also quite high, indicating very good integrity of older sections of pipe in the Township, despite its age, as well as replacement sections.

In addition to the hydrotesting performance factors, Accufacts also reviewed information related to pipe replacements in the Township as well as Sunoco's ILI approach in re-qualifying the pipeline in the Township for the new operation. A review of Google Earth and alignment maps across the Township did not reveal any threat factors such as land movement that could result in abnormal loading pipeline failure. Accufacts has found no significant anomalies that could affect the pipeline in the Township segment to cause growth to rupture failure in the reasonable future, and concludes that Sunoco's ILI assessment management approaches are prudent.

The primary objective of an integrity management program is for the pipeline operator to undertake efforts to avoid pipeline failure in high consequence areas, such as the Township, from various types of threats that may be present on such sensitively located pipeline segments. It is Accufacts' opinion for the section of 8-inch pipeline that crosses the Township, that Sunoco far exceeds a number of requirements of the federal pipeline safety regulations, that it embraces the intent of integrity management, or IM, regulations that are meant to prevent pipe mainline rupture failure, and that their IM approach is currently prudent.

3. Operation of the Mariner East Pipeline affecting the Township

Components of the pipeline other than the mainline pipe in the Township play an important role in the operation of the HVL pipeline as it could affect the Township. These include: 1) the Boot Road Pump Station located within the Township, 2) upstream and downstream pump stations and mainline pipe beyond the Township, 3) certain mainline valves and their actuation, and 4) to a lesser extent, the elevation profile of the pipeline.

3a) The Boot Road Pump Station

There are certain minimum pump station requirements in federal regulation that set important obligations that the pipeline operator: a) have the station under their control (i.e., fenced boundaries), b) require the installation of certain emergency and fire protection equipment, and c) install separate power supplies that will allow the emergency shutdown of the station

⁴ 49CFR§195.304 Test pressures.
Accufacts Inc.

by the pipeline operator.⁵ With these additional requirements in place, while a failure/release in a pump station can be fairly spectacular, the release tonnage from a station failure is much more limited than that from a mainline pipeline rupture failure. At Accufacts' request, Sunoco provided Boot Road Pump Station piping and instrument diagrams ("P&ID") that identify the general existing and new additions to the station, indicating piping size and flow arrangements within the station, as well as key instrumentation and various safety approaches for the station. The Mariner East pump stations, including the Boot Road Pump Station, are designed to be shut down in an emergency, or ESD, either locally, remotely from the control room, or automatically via the computer system, isolating line segments if needed.

Based on a detailed review of the P&ID, Accufacts observes prudent pump station design that properly incorporates safety protection reflective of an HVL product operation, and also includes additional well thought out protections for the mainline in the event the pipeline is shut down. Some of this safety design requires the installation of a flare at the Boot Road Pump Station. This flare will have three types of operation:

- 1) a continuous pilot light within the flare to assure reliable ignition of combustibles that may be directed to the flare at any time;
- 2) an intermittent burn of smaller thermal or maintenance venting of pipeline/pump station equipment periodically released to the flare; and,
- 3) an intermittent burning of larger volumes of combustibles to quickly de-inventory segments of the pump station and sections of connecting mainline during an emergency.

Accufacts concurs with Sunoco's safety approach regarding integrating a flare into the pump station. Accufacts is well aware of public concerns regarding the installation of a flare at the Boot Road Pump Station, but Accufacts concurs that the flare is needed for various prudent safety reasons that cannot be publicly disclosed in detail.

The pump station flare should not often be operated at a high volume. Some of the public may be acquainted with flare operations associated with larger refinery flares that can generate considerably more heat and noise than the proposed flare at Boot Road. Although future pump station modifications from other pipeline projects (Mariner East 2) might increase flaring potential, the Boot Road Pump Station flare should not be operated as frequently as a refinery flare. Should such an integration occur from another project, it should still be a fairly infrequent safety operation. Basically, the Boot Road Pump Station

⁵ 49CFR§195.262 Pumping equipment.
Accufacts Inc.

flare is needed to reduce volumes of combustibles that could be released into the environment in close proximity to the public in the Township. Accufacts thus concludes Sunoco's flare approach is fair and appropriate.

3b) Pipeline Mainline Valve Remote Actuation

Accufacts has reviewed the pipeline elevation profile provided by Sunoco that also identified various additional pump stations and mainline valve locations along the pipeline outside of the Township. The installation/placement of remotely operated valves along a pipeline, especially in an HVL pipeline, is not an exact science. In case of pipeline rupture, material in HVL pipelines (unlike most liquid pipelines) can flow uphill. This has made the development of regulations concerning the placement of such important valves subject to some interpretation, with a wide field of opinions. There is no absolute "one size fits all" solution to the placement of mainline valves on liquid pipelines, especially because valving with remote actuation can introduce additional operational complexities for a pipeline if an appropriate safety review has not been performed (such as surge analysis and thermal expansion potential) and incorporated into the installation.

Accufacts has recommended that two mainline valves that were installed as manually operated isolation valves beyond the Township be actuated to permit remote and automatic mainline valve closure, isolating segments of the pipeline in an emergency. Sunoco's acceptance to remotely actuate two suggested existing manual mainline valves that span the Township, but are not within the Township boundaries, is a reasonable and necessary precaution and provides an additional level of protection to Township residents in the case of an emergency.

3c) Automatic and Remote Pipeline System Shutdown

Given its criticality to the overall operation of a high pressure HVL pipeline system in a highly populated area, Accufacts spent considerable time and effort reviewing and discussing with Sunoco's technical experts the system to automatically shut down the pipeline in the event of a possible rupture release. Sunoco information indicates that upon certain trigger events, usually indicative of a possible pipeline rupture, the Mariner East pipeline and pump stations will be automatically shut down, and the stations and segments of the mainline automatically isolated by strategically placed mainline valves closing. Sunoco further informs me that this important system-wide safety approach also covers major transients such as those that can occur during startup and shutdown, and major product changes. The control room operator can also manually initiate the automatic shutdown of the pipeline system.

3d) "Leak Detection" Systems

There are basically two types of pipeline releases, leaks and ruptures. Leaks are smaller rate releases from such conditions as minor cracks, pitting corrosion holes, punctures etc., where the minor size of the opening limits the rate of release. Leaks can nevertheless be dangerous depending on where they occur. The other type of releases are ruptures, high rate releases associated with large openings in the pipe caused by pipe fracture from certain anomalies or imperfections in the pipe. Ruptures by their nature are always dangerous,

Because of the complexity of hydrocarbons and pipeline operation, it is very difficult to design and install a leak detection system that can remotely identify all forms of pipeline releases. Accufacts advises that pipeline operators first focus on remotely identifying pipeline ruptures, and then attempt to improve on technology to possibly identify the much harder to recognize leaks. It is a significant challenge to reliably identify rupture releases, and technology has not yet been developed to dependably identify pipeline leaks. Too often Accufacts has observed pipeline operators trying to operate leak detection systems to capture all forms of releases only to be faced with excessive nuisance false release alarms. Leak detection approaches that generate such excessive false alarms, leak or rupture, set up control room operators to miss or ignore real release events when they occur. Accufacts has repeatedly observed in its investigations excessive false leak alarms causing control room operators to miss even pipeline rupture events.⁶ One of the objectives of the control room management regulation promulgated in 2009/2010 was to assist the operators in removing such excessive false alarms.⁷

Regarding "leak detection", the Mariner East project will first incorporate an advanced computer/automatic system that scans and monitors the pipeline and pump stations for certain parameters that are indicative of a possible pipeline rupture, and automatically initiates a full pipeline system shutdown and isolation, including pump station isolation and remote mainline valve closure, following a special required sequence. Sunoco information provided indicates a rational and progressive approach in trying to achieve pipeline rupture release detection with automated shutdown response without excessive false alarms. It is Accufacts' experience that Sunoco's particular approach may cause more false shutdowns than simple leak detection, but Sunoco has applied the use of this design that includes transient detection on their Mariner West operation, and false shutdowns have been very infrequent on that system since its startup slightly more than a year ago.

⁶ National Transportation Safety Board, NTSB, "Enbridge Incorporated Hazardous Liquid Pipeline Rupture and Release Marshall, MI July 25, 2010," NTSB/PAR-12/01, adopted July 10, 2012.

⁷ 49CFR§195.446 Control room management.
Accufacts Inc.

To complement the automatic shutdown system focused on possible larger pipeline releases, the pipeline will also incorporate a different separate non-automatic "leak detection" software package that is intended to assist the control room operator in possible pipeline leak as well as rupture identification. To enhance the effectiveness of this software leak detection system the pipeline is to be normally operated liquid full, or non-slack line. This separate approach requires the control room operator to interpret presented information of a possible release in a special format, decide if a possible release indication is real, and manually initiate a system wide shutdown if warranted. This second leak detection monitoring system relies on control room operator intervention, but is intended to supplement the automatic shutdown intended for larger releases.

Accufacts supports Sunoco's approach for both automatic shutdown and isolation for large releases, and the second "leak detection" approach that requires the control room operator to evaluate certain presented information and determine if a possible pipeline release is occurring, and manually initiate a pipeline shutdown.

3e) The Critical Role of the Control Room Operator.

While pipeline automation plays an important role in controlling and monitoring certain aspects of a pipeline operation, and can play a timely safety role in automatically shutting down and isolating a pipeline system, the control room operator nonetheless still serves an important function in pipeline operation. The control room operator is responsible for managing various operating parameters, as well as monitoring and responding to various computer signals, including responding to alarms, in their hierarchy of importance. A well designed computer system that initiates certain actions such as automatic shutdown and mainline valve closure can react faster than a human monitoring various aspects of a pipeline system. Such complexity should not override the ability of the control room operator to initiate a shutdown if he feels it is warranted. Accufacts considers Sunoco's computer monitoring and shutdown approach to be "progressive" in its efforts to assure a safe and prompt response in the event of a HVL rupture release, should it ever be needed.

Even in a system designed for automatic shutdown, the control room operator has an important role to assure that the safety equipment has performed as intended, especially in the case of a system-wide automatic shutdown. Accufacts did not see in Sunoco's original emergency procedure that, upon such an automatic shutdown, the control room operator is instructed to check the overall pipeline system to assure that the pump stations have shut down and that automatically operated valves along the mainline have properly closed to assure segment isolation. In too many pipeline rupture investigations, Accufacts has found deficient operating procedures that do not require the control room operator to assure remotely operated/actuated mainline valves have been quickly and properly closed. Sunoco has agreed to add a modification to their control room emergency procedures to assure that

the operator checks that the emergency shutdown system has performed as intended, and that mainline valves have properly closed.

3f) The Importance of Emergency Response Plans

Pipeline operators are required under federal pipeline regulation to have emergency response plans to deal with the emergencies associated with pipeline releases. Such procedures focus on protecting people first and then on property, establish who is in control and how control is handed off during various stages of a release, what type of command structure is utilized for such emergencies such as the Incident Command Structure (or ICS) that has proven to be highly effective in pipeline releases, and how communication is maintained with first responders who are usually the first to arrive at a release site. It is important that all key pipeline personnel be trained in their various roles and responsibilities in the event of a pipeline release emergency, especially pipelines moving HVL that can have serious consequences.

During an emergency involving a release, the control room plays a critical role as the emergency contact actually controlling and monitoring the pipeline to assure that appropriate equipment has been properly shutdown. The control room also serves to maintain liaison with local emergency responders until hand-off to company onsite field incident command personnel can occur. The control room thus is a critically important initial contact with local emergency responders to assure everyone is properly communicating/coordinating during the important initial stages of a possible pipeline release where there can be much confusion.

Under federal pipeline safety regulations, the pipeline operator is required to notify and coordinate with emergency first responders during pipeline emergencies.⁸ The control room should have a list of local emergency contacts, including "other public officials." Local first responders and these officials should also have company emergency contacts and, for obvious reasons as identified above, the important pipeline control room emergency contact number(s). Because of various changes that may occur in organizations, local official contact numbers can be frustratingly difficult to keep current, but the control room contact number should usually never change. Federal pipeline safety regulations place the responsibility to keep emergency contacts with Township officials squarely on the pipeline operator for very good reasons.⁹ It is Accufacts' understanding that these important contacts for the Township have been recently updated and that Sunoco has a process for periodically updating the list.

⁸ 49CFR§195.402 Procedural manual for operations, maintenance, and emergencies.

⁹ 49CFR§195.402(e)(7).

4. Keeping Township Informed of Future Major Changes in the Pipeline's Integrity within the Township

As discussed above, a prudent safety management approach should initially assess the integrity of the pipe, periodically reassess the pipe for possible new threats, and install appropriate equipment to allow the monitoring and shutdown of the pipeline during a suspected possible emergency. At Accufacts' recommendation, Sunoco has agreed to keep the Township informed of a future possible integrity threat on the pipe within the Township identified under 49CFR§452(h)(4) (i), (ii), (iii), & (iv), *Special requirement for scheduling remediation*, once it has been discovered by the operator.¹⁰ Based on Accufacts' extensive experience this reporting requirement should assist the Township to know that the pipeline operator continues to utilize a prudent integrity management approach to avoid threats of possible pipeline rupture failure on the segments in the Township. It again should be stressed that no pipeline is anomaly free, even new pipelines, so anomalies should be expected. The key is to catch those anomalies that can quickly lead to failure, especially rupture. The federal regulatory requirements as to identified threats for which the Township will receive notice should be sufficient, and reporting any changes should not be difficult or burdensome on either the pipeline operator or the Township.


5. Accufacts' Conclusions

As discussed above, the important hydrotesting protocols utilized in November 2014 by Sunoco on the Mariner East pipeline exceed federal regulatory protocols in the application of strength hydrotesting at adequate pressures and in % SMYS. In addition, Sunoco performed an important spike hydrotest which is not currently required by pipeline safety regulations. Accufacts finds that Sunoco exceeds federal hydrotest regulatory requirements and complies with the latest PHMSA Advisory Bulletin concerning pipeline reversals as discussed earlier (ADB-2014-04). These special hydrotest approaches play an important role in assuring the integrity of the pipeline at the time of the hydrotest, even for very old pipe.

It is also Accufacts' opinion that Sunoco, on the Mariner East pipeline segment that could affect the Township, is exceeding federal pipeline safety regulations in utilizing additional integrity management approaches, prudent pump station design, mainline valve placement and actuation, pipeline monitoring, as well as control room procedures, automatic release detection safety systems, and emergency notification protocols that reflect the level of respect that transporting HVL should require in a prudent pipeline operation. While these efforts cannot guarantee against a release, they reflect a safety attitude that applies up to date

¹⁰ 49CFR§452(h)(2) *Discovery of condition* places an upper time limit of 180 days from an integrity assessment (e.g., ILI) for the threats that might be introduced in the future operation of Mariner East that can affect the Township.

steps to avoid a release and respect for the consequences a material release could produce, especially rupture. Accufacts concludes that the Mariner East phase 1 project, with the enhancements discussed above, meets or exceeds the prudent technical approaches commensurate with the safe transportation of HVL.

A handwritten signature in cursive script, reading "Richard B. Kuprewicz". The signature is written in black ink and is positioned above the printed name.

Richard B. Kuprewicz
President,
Accufacts Inc.

APPENDIX 6

List of Members of Concerned Citizens of West Goshen Township

Members of Concerned Citizens of West Goshen Township
(All addresses are in West Chester, PA 19380)

Raymond and Holly Allen
1244 Killern Lane *Yes Proxy*

Amanda and John Buffington
1008 E. Boot Road

Mike and Carol Burkardt
1246 Victoria Lane *CB*

RL Rosana I. Chiple
1130 Laurel Drive

Derick Deangelo
1256 Victoria Lane

MD Marcella and Mark Denisewicz
1312 Mary Jane Lane

Keith Dickerson *(i:an)*
1212 Culbertson Circle

LD Linda Erfle
1237 Killern Lane

[REDACTED]

Christine & Ted Frain
1252 Victoria Lane

Georgine Guzzi
1303 Anderson Ave *gr*

Leonard J Iacono *LI*
1324 Mary Jane Lane

Leonard Kelly *LK*
1313 Mary Jane Lane

Kevin and Krista Link *KL & KL*
1315 Mary Jane Lane

Mark and Mary Jane Lorenz
1317 Mary Jane Lane

EMM Eric and Lizann Marchetti
1308 Mary Jane Lane

DMS
KMS

Drew & Kimberly McCorkell
1303 Mary Jane Lane

James & Mary Meyers *JM*
1309 Mary Jane Lane

Steve and Lynn Moose *THH*
1235 Hamlet Hill Dr. *OR*

EMM Erin Morelli
1322 Mary Jane Lane

Anthony Natale III
1254 Victoria Lane

John & Mary Nescio
1307 Mary Jane Lane

Cindy & Tim Nichols *CTN*
1223 Hamlet Hill Drive *TR (SJR)*

SM Sharon Owen *RR for Sharon Owen*
1304 Mary Jane Lane *Proxy*

Tom Pavletich
1132 Laurel Drive

Jeff Perham *JF (SJR)*
1221 Trafalgar Lane

Joseph & Deborah Radzewicz *JR DR*
1248 Victoria Lane *(SJR)*

Phyllis Ruggiero
1311 Mary Jane Lane

Masooda B. Siddiqui *MS*
1325 Mary Jane Lane

Diane Watson Treon
1320 Mary Jane Lane

Edna Mae Veit *EV*
1314 Mary Jane Lane

Exhibit B

Phone: (215) 569-5793
Fax: (215) 832-5793
Email: Lewis@BlankRome.com

February 14, 2017

BY EMAIL & U.S. MAIL

David Brooman, Esquire
High Swartz LLP
40 East Airy Street
Norristown, PA 19040

Re: **Settlement Agreement between West Goshen Township and Sunoco Pipeline L.P.**

Dear David:

Following our telephone conversation yesterday afternoon, I am writing you to provide written assurance that Sunoco Pipeline L.P. (“SPLP”) fully intends to live up to its plan, as stated in the Settlement Agreement, to automate the valve at pipeline marker 236.6. Currently, SPLP expects the work on the valve to be completed by March 31, 2017.

While the citizens of West Goshen Township (the “Township”) may be disappointed that the work was not completed earlier, SPLP has proceeded with the installation of this remotely controlled valve as expeditiously as possible given the circumstances surrounding the necessary rights of way. We would hope that, in the interest of preserving its limited resources, as well as those of the Public Utility Commission (the “PUC”), the Township would avoid initiating a legal dispute that is clearly moot. The PUC has repeatedly emphasized that its policy is to encourage mediation and settlement rather than to see the parties engage in what may become lengthy and expensive litigation during a formal hearing process. Please note that the expense of such a proceeding would be borne by the Township’s taxpayers, inasmuch as the PUC has no authority to award damages, attorneys’ fees or costs. *Edward Kovler and Elena Glzman v. PECO Energy Company*, Docket No. C-2013-2365555, 2013 WL 6248460 (2013).

As regards the relocation of the valve station, the Settlement Agreement expressly states “[i]f due to engineering constraints, SPLP is unable to construct the valve station in the SPLP Use Area, SPLP will notify WGT.” There is no provision in the Settlement Agreement requiring the Township’s approval of the new location. Nevertheless, it is my understanding the SPLP has consulted with Kristin Camp, the Township Solicitor, and Casey LaLonde, the Township

David Brooman, Esquire
February 14, 2017
Page 2

Manager, to notify them of the new location and in an effort to address any aesthetic concerns that might arise from the new location.

In addition, both the timing of the installation of the remotely operated valve at pipeline marker 236.6 and the relocation of the valve site were discussed with Mr. Richard Kuprewicz, the safety expert retained by the Township, as part of his safety review of the Mariner East 2 project.

As to both of the above issues, SPLP has been trying to schedule a telephone call with you, Kristin Camp, and Casey LaLonde to provide relevant information, listen to any concerns, and amicably resolve any potential areas of disagreement. We will continue to try to schedule this call as soon as possible.

Very truly yours,



Christopher A. Lewis

CAL:arc